



# Biopharma MFG Facility Site MFG Operational Readiness Activities



# Overall Manufacturing Operational Readiness Key Activities

## MFG Operational Readiness Activities

- Define Biopharma Process/ Equipment-Systems
- MFG Batch Records, Sampling Plans, & BOM
- SOP's-Forms, Work Instructions, & Training
- QC Labs Methods & Equipment

## Tech Transfer Readiness Activities

- Process Flow Drwgs/ Critical Process Parameters
- Define MFG Process Equipment/ System
- MBR-Forms, Work Insts, Sampling Plan, & BOM

## Supply Chain Readiness Activities

- Establish GMP Warehouse SOP's & Forms
- Establish Raw Materials, Gowns, & Consumables
- Establish Supplier Quality Management SOP

## Quality Readiness Activities

- Establish Quality Manual, QMS SOP's, & Forms

## Engineering-Facilities Readiness Activities

- CMMS Equipment-System Integration
- Calibration, HEPA Certification, & TOP Verification
- MFG Facility & Support Areas Mechanical Completion
- Cleanroom Final Balancing & Certification
- IT Systems: BMS, EMS, CMMS, ERP, & ELN

## Validation/ Commissioning Readiness Activities

- MFG Facility EMPQ, Process & Support Systems
- Commissioning Plan: Utilities/ HVAC Systems/ BMS
- JIT GMP Warehouse & Support Areas
- Facility Readiness (Floors/ Walls/ Ceilings)

## QC Labs Readiness

- QC Lab Equipment-System List
- QC Labs SOP's/ Forms & ELN System (LIMS)
- QC Labs Equipment/ Method Validation

## Resource Plan

- Resource Hiring Plan, Training Plan, & Safety Plan

# Biopharma MFG Facility Project Management Tools

## Integrated Project Schedule:

- ❑ MFG Facility Design, Construction, Commissioning, Validation, MFG OPS, & Released for MFG: Key Project Milestones

## SOPs/ Forms Tracker:

- ❑ SOPs/ Forms Development, Review, and Approval: Departments, Owners, Reviewers, Approvers, and dates

## MFG Facility Site Equipment Tracker:

- ❑ MFG Facility Site Equipment Tracker: Dept., Model/ Make, Capacity, New, Relocate, Order, Receipt, Install, Cal, Cx, & VAL

## Biopharma MFG Facility Operational Readiness Dashboards:

- ❑ Commissioning Readiness Dashboard: Testing, SATs, Build Field Verification, Final Balancing/ HEPA Cert, TOP, & Cx
- ❑ Validation Readiness Dashboard: Clean Utilities, Equipment/ Systems, QC Labs, & GMP Warehouse Validation Activities
  - ❑ EMPQ Readiness Dashboard: Biopharma MFG Facility Cleanrooms EMPQ Activities
- ❑ Facilities-Engineering Readiness Dashboard: Implement CMMS System (PM, Calibration, HEPA Cert), Safety, & Utilities
- ❑ Supply Chain/ GMP Warehouse Readiness Dashboard: Controls, Materials, Consumables, Resources & ERP
- ❑ MFG Readiness Dashboard: MFG Equipment, MBRs, Sampling Plans, BOMs, Training, Resources, & Tech Transfer
- ❑ Quality Manual/ QMS Readiness Dashboard: QMS SOP's, Forms, Specifications, EDMS, Resources & QC LIMS
- ❑ QC Labs: Labs Equipment, QC ELN System VAL, Training, Resources, & Analytical Method Validation

# Construction/ Commissioning Operational Readiness Activities

## Construction/ Commissioning

- Construction Mechanical Completion (MC) Oversight
- Define Master Equipment/ System List
- Order Process Equipment/ Systems
- Equipment Receipt Verification (ERV)
- Author/ Approve Commissioning (Cx) Activities
- Asset Induction CMMS (PM's/ CAL/ HEPA Certs)
- Pre-Mechanical Completion (PMC) Field Verification against design drawings/ URS's
- Mechanical Completion (MC) Field Verification

## Construction/ Commissioning

- Verify/ Approve General Contractor Turn Over Package (TOP)
- Verify Operations/ Maintenance Manual Library and support SOP's
- Manage the Calibration execution
- Verify Equipment/ System Startup/ SAT
- Execute Utility/ HVAC System Function Testing
- Oversee the HEPA Certification/ HVAC Balancing
- Manage the HVAC System/ Utility Training Development and Execution
- Generate/ Approve Cx Protocols & Reports

# Manufacturing Operational Readiness Activities

## Safety & Compliance

- Permits & Licenses
- Blood Borne Pathogen/ Vector/ Raw Materials

## GMP Document Management

- EDMS (Veeva/ Master Control)
- SOP-Forms/ Work Instructions Master List
- Bill of Materials (BOM)
- Manufacturing Batch Records (MBR)/ Forms
- Sampling Plans

## GMP Warehouse/ Materials

- Material Management Systems (Oracle/ SAP)
- Supplier Quality Management SOP

## QC Labs Readiness

- QC Lab Equipment-System List
- QC Labs SOP's/ Forms & ELN System (LIMS)
- QC Labs Equipment/ Method Validation

## Tech Transfer Readiness Activities

- Process Flow Drwgs/ Critical Process Parameters
- Define MFG Process Equipment/ System
- MBR-Forms, Work Insts, Sampling Plan, & BOM

## Engineering/ Facilities

- Final As Built Drawings
- Mechanical Completion Field Verification
- Asset Induction into CMMS
- HVAC Systems/ Utilities Function Tests
- Cleanroom Final Balancing & Certification

## Validation Master Plan/ Cx Plan

- Master Equipment List with Val Requirements
- Execute Validation & Cx Risk Assessments
- EMPQ Execution Strategy
- QC Labs Equipment/ Method Val Requirements

## Resource Plan

- MFG/ ENG/ QA/ QC & WH Training Strategy

# Validation Plan Operational Readiness Activities

## Validation Plan (MFG/ QC Labs/ GMP Warehouse) Operational Readiness Activities

- ❑ Finalize Master Equipment/ System List
- ❑ Develop and the manage the execution of the Validation Plan
- ❑ Execute VP Risk Assessments
- ❑ Develop/ Approve Design Qualification based on BOD & URS's
- ❑ Design/ Approve CTF & Support Areas P&ID's
- ❑ Develop Operational SOP's/ Forms
- ❑ Develop CTF, Support Areas, & GMP Warehouse Equipment/ Systems SOP's/ Forms
- ❑ Develop/ Execute Cell Therapy Facility EMPQ


## Validation Plan (MFG/ QC Labs/ GMP Warehouse) Operational Readiness Activities

- ❑ Execute Equipment/ System IQ, OQ, & IOQ
- ❑ Execute Equipment/ System IOPQ's & PQ
- ❑ Manage the MFG, ENG, QA, QC, & VAL Process Training Development and Execution
- ❑ Qualify/ Validation QC Labs Analytical Equipment and Methods
- ❑ Execute Media Simulation PQ's
- ❑ Execute Shakedown/ Engineering Runs
- ❑ Execute GMP Runs
- ❑ Execute PPQ Runs



# Quality Manual/ Quality Management System

## Quality Manual



## Quality Management Systems

- Quality Policies
- Quality Risk Assessment
- Commissioning/ Validation
- Change Control
- Deviation/ CAPA
- Document Control
- Internal/ External Audits
- Supplier Qualification Management
- Clinical Quality
- Commercial Quality
- Management Review
- Record Management/ Retention
- Supporting Quality Procedures

# Biopharmaceutical Site Automated Systems

- **Building Management System:** HVAC System, AHU's, Exhaust Fans, Temperature, and Humidity (Delta, Johnson Controls, etc.)
- **Environmental Monitoring System:** Cleanroom Pressure, Temperature, and Humidity/ GMP Warehouse Temperature (Delta, Environmental, Johnson Controls, etc.)
- **Computerized Maintenance Management System:** Equipment PM's, Repairs, Calibrations, and HEPA Certifications (Blue Mountain, Maximo, etc.)
- **Biopharmaceutical Site Door Access Control System**
- **QC Labs Systems:** Electronic Notebook, Lab Consumables, LIMS Data, Sample Management (Labware, Thermo, Horizon, etc.)
- **Materials Management System:** (ERP: Oracle, SAP, SAGE)
- **Security and Fire Systems:** Cameras, Dual Action Dry Fire System, Water Fire System